

2017 Hollywood Truck Haul Project Project Information Data Sheet

The Hollywood CRA contracted Applied Technology & Management (ATM) to assess the City of Hollywood's beaches to determine whether beach fill can be placed within the previously permitted (2011) beach template. ATM conducted surveys and assessed the condition of the beaches. It was determined that of the two segments permitted in 2011, only the south segment (from approximately Crocus Terr. to the south City Limit) could receive sand. A one-time placement of material above the Mean High Water line was granted through a permit modification to include approximately 2000 feet of shoreline at the northern City Limits.

- Placement of +/- 66,000 Cubic Yards of sand to be placed in the two segments.
- Sand will come from the Witherspoon Quarry, Moore Haven, FL.
- Sand will be trucked to two beach accesses
 - Meade St. and Custer St. for the north segment – No Parking beginning 12/18 (for 1 week).
 - Magnolia Terr. and Keating Park for the south segment – No Parking beginning 1/2/18 for through February 28, 2018.
- Work Hours:
 - Monday – Friday from 7:00 am to 6:00 pm (no Saturday work is planned)
- Work will begin the week of December 18th in the north segment.
- Work will work around the holidays.
- South Segment to begin after the New Year.
- Beaches will be open during construction, only immediate work areas will be closed and fenced for safety.
- Total project timeframe is approximately 6-8 weeks. Planned completion prior to 3/1/18.
- Estimate 100-150 truckloads of sand per day (3600 total trucks/project).
- Contractor: Eastman Aggregates
- Project Oversight by Applied Technology & Management
 - John Waszak – 954-288-1072

